

**Town of Bleecker**

Permit # \_\_\_\_\_

**SEPTIC SYSTEM APPLICATION**

**Application is for:**

- New Construction of a private dwelling
- Alteration or enlargement of an existing system
- New Construction of a commercial building

**Number of Bedrooms:** \_\_\_\_\_

**Garbage Disposal** Yes \_\_\_\_\_ No \_\_\_\_\_

**Topography:**

- Flat
- Rolling
- Steep Slope
- Gentle Slope
- Other \_\_\_\_\_

**Nature of Soil:** (Describe to a depth of 5 feet for a tile field and 10 feet for leaching pits)

\_\_\_\_\_

**Percolation Rates:**

1.
2.
3.
4.
5.
6.

**Percolation Test Performed By:** \_\_\_\_\_

**Septic System Requirements:**

- Minimum Tank size 1000 gallons
- 100 ft. separation between leach field and any well, body of water or wetland
- 150 ft. separation between any leaching pit and any well, body of water or wetland
- 10 ft separation between system component and property line or right of way
- 10 ft separation between septic tank and building
- 20 ft separation between house and distribution box
- Maximum length of absorption line (gravity fed) is 60 ft.
- Adjacent absorption trenches to be separated by at least 4 ft. of undisturbed earth

**Applicant:** \_\_\_\_\_

**CEO:** \_\_\_\_\_

**Date:** \_\_\_\_\_

Approved  Denied **Date:** \_\_\_\_\_